

The requirements stated below are approximate and are in support of the peculiar refueling system of two KDC-10s at Eindhoven AB, The Netherlands.

A. Office space (Based on three personnel in support of Peculiar systems):

Office area for FSRs	606 Sq Ft
----------------------	-----------

B. Spares and test equipment storage:

Boom Storage 14’x50’	
Spares area 20’x30’x16’	600 Sq Ft
Test equipment area 10’x20’x16’	<u>200 Sq Ft</u>
Total Spares & Test Equipment (excluding boom storage)	800 Sq Ft

C. Bench stock space required:

Three Stanley Vidmar cabinets 2.5’x2.5’x5’ to hold bench stock and small parts	<u>36 Sq Ft</u>
Total Bench Stock	36 Sq Ft

D. GSE parking and repair space required (Boom storage area of 14’x50’ included in repair area):

Boom repair area 14’x70’x16’ Support equipment parking space 30’x40’ General repair area 20’x30’x16’	
Total GSE	2880 Sq Ft

Note: GSE repair area requires access to 28 volt/400 cycle power.

E. Shipping/Receiving/Packaging/Inspection:

Shipping/Receiving 15'x20'

Total Shipping/Receiving 300 Sq Ft

F. Workshop space for repairs/inspections:

Workshop space is to be provided in RNLAF shops on an as required basis to support welding, sheet metal, and minor fabrication repairs. All other space is included in paragraph d. GSE repair.

G. Activities essential to be performed inside: All activities must be performed inside with the exception of GSE parking which could be outside, weather permitting.

H. Additional criteria:

- (1) Vehicle parking for customer (issue/turn-in), COMBS (pickup or van) and personnel (private/company auto).
- (2) Communications: Four telephone lines will be available. Two for FSR communications, one for FAX, and one for computer modem.
- (3) Lighting: Repair areas require 40 lumens and warehouse area require 25 lumens.

The total square footage estimate is 4346 sq ft. A facility 60' wide X 70' long X 16' high = 4200 sq ft should be adequate to provide the required space for LMAC COMBS requirements. This is an estimate and will require updating when the actual requirements are known.

NOTE: It is understood that figures contained herein are approximate and are not to be construed as requiring exact compliance. Substantial compliance (+/- 10% of listed figures) shall be deemed to have satisfactorily fulfilled these requirements.

